

15-163-30164-0000

Form CP-3  
Rev. 6-26-62

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Operator's Full Name Frontier Oil Company

Complete Address: 1720 Wichita Plaza Wichita, Kansas

Lease Name Dick Well No. 3

Location NW NW NW Sec. 17 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3778

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated:     

Plugging Contractor: Red Tiger Drilling Co.

Address: Wichita, Kansas License No.     

Operation Completed: Hour 5 P Day 21 Month 6 Year 1966

The Above well was plugged as follows:

RTD 3778 8 5/8 at 219 cw 140 sc cement circulated.

Gunned pits, circulated heavy mud, set cementing plug at 540 and displaced 20 sc

cement thru drill pipe. Heavy mud to 210 and displaced 20 sc cement thru drill pipe.

Heavy mud to 40 Ft. set cementing plug, 1/3 sc hulls and 10 sc cement to base of

celler. Plugged rat hole with 2 sc cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-24-66  
JUN 24 1966

I hereby certify that the above well was plugged as herein stated.

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

Signed: Leo Massey  
Well Plugging Supervisor

DATE 6/29/66  
INV. NO. 3463-W