

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT REPORT

API Number 15-163-21, 796-0000

200 Colorado Derby Building  
Wichita, KS 67202

Operator's Full Name MURFIN DRILLING COMPANY

Complete Address 617 UNION CENTER BLDG. WICHITA, MO. 67202

Lease Name THOMAS Well No. # 2-18

Location 475' F.S.L - 550' F.E.L. Sec. 18 Twp. 10 Rge. 19 (East)(West)

County ROOFS. Total Depth 3858 FT.

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor MURFIN DRILLING CO. (LOYD DELLETT)

Address 617 UNION STR. BLDG. WICHITA, MO. 67202 License No. \_\_\_\_\_

Operation Completed: Hour: 3:00 AM Day: 11<sup>th</sup> Month: SEPT. Year: 19 82

Plugging Operations attended by Agent?: All  Part  None

The above well was plugged as follows:

8 5/8" - 301 FT SR. CUC. w/200<sup>st</sup> SUN SET (BY SUN CMT.)  
ORDERED 160<sup>st</sup> 50/50 FORMIX 6% GEL - 3% PA-CL. AND 8 5/8" PLUG.  
SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.  
1<sup>st</sup> PLUG @ 1050 FT w/ 100<sup>st</sup> CMT.  
2<sup>nd</sup> PLUG @ 300 FT w/ 40<sup>st</sup> CMT.  
3<sup>rd</sup> PLUG -> SOLID BRIDGE @ 40 FT w/ 10<sup>st</sup> CMT.  
10<sup>st</sup> IN RAT HOLE (CIRCULATE)  
CEMENTED BY SUN CMT.

Amount of Surface Casing: 301 FT.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]  
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

RECEIVED  
STATE CORPORATION COMMISSION  
9-27-82  
SEP 27 1982  
CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

DATE 10-20-82

INV. NO. 1426-W

Signed: \_\_\_\_\_  
Conservation Division Agent

B