

15-163-01939-0000

Form CP-3
Rev. 6-4-68

KANSAS

AP
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
10-16-72
OCT 16 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Oklahoma Fracturing Services, Inc.

Complete Address 630 United Founders Life Tower Oklahoma City, Oklahoma 73112

Lease Name Anderson Well No. 2

Location SE SE NW Sec. 18 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3890'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Knight Casing Pulling

Address Box 405 Chase, Kansas 67524 License No. 436

Operation Completed: Hour 10:30 A Day 13 Month 10 Year 1972

The above well was plugged as follows:

- Total Depth 3890' 10 3/4 csg set at 275' cwc
- 7" csg set at 3890' cw 250 sk cmt.
- 7" csg PBD 3853 with top perf. (3782)
- Filled 7" csg W/sd (3750-3890) Dumped 6 sk cmt W/dump bailer. (3715-3750)
- Cutoff and recovered 900' of 7" csg.
- Pumped down 10 3/4 csg with 15 sk gel & water W/300 lbs hulls - 50 sk cmt - 10 sk gel & water - released 10 3/4 plug and pumped 80 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED
DATE 10/17/72
INV. NO. 6498-W