

15-163-01966-0000

Form CP-3  
Rev. 6-4-68

KANSAS

*2* STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
10-16-72  
OCT 16 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Oklahoma Fracturing Services, Inc.  
Complete Address 630 United Founders Life Tower Oklahoma City, Oklahoma 73112  
Lease Name Anderson Well No. 8  
Location NE SE NW Sec. 18 Twp. 10 Rge. (E) (W) 19  
County Rooks Total Depth 3785'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Knight Casing Pulling  
Address Box 405 Chase, Kansas 67524 License No. 436  
Operation Completed: Hour 12 M        Day 13 Month 10 Year 1972

The above well was plugged as follows:

Total Depth 3785' 10 3/4 csg set at 188' cwc 200 sk.  
7" csg set at 3781' cw 250 sk cmt.  
7" csg PB & perf. (3611)  
Filled 7" csg W/sd to 3600' -Dumped 6 sk cmt W/dump bailer. top of cmt. 3550'  
Cutoff and recovered 697' of 7" csg.  
Pumped down 10 3/4 csg with 15 sk gel & water W/300 lbs hulls - 50 sk cmt - 10 sk  
gel & water - released 10 3/4 plug and pumped 80 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Messing  
Well Plugging Supervisor

DATE 10/17/72  
INV. NO. 6479-W