


KANSAS



STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 6 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name O. F. S., Inc.,

Complete Address: 630 United Life Tower Bldg., Oklahoma City, Oklahoma

Lease Name Anderson Well No. 11

Location SW NE NE Sec. 18 Twp. 10 Rge. 19 (E) (W) X

County Rooks Total Depth 3660'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Murfin Drlg.

Address: Wichita, Kansas License No. _____

Operation Completed: Hour 7:30 A Day 1 Month 5 Year 1968

The Above well was plugged as follows:

RTD 3660' 8 5/8 csg set at 251' cwc. 150 sc. Cem. Mat. 100 sc of 6% 50-50 poz cement.
Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 5/7/68
INV. NO. 7703/w

Signed: Geo F. Massey
Well Plugging Supervisor