

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
211 North Broadway
Wichita, Kansas

FILE NO. 39-29

LOCATION NE SE SE

SEC. 18 TWP. 10 RGE. 19

Dry Hole _____ Abandoned Oil Well X Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Foulke

Operator Morganstern - Specter Address Russell, Kans

Field _____ County Rooks

Total Depth 3784 Feet.

Plugging Contractor Forbes Casing Pulling

Plugging Contractor's License No. 49

Address _____

(Describe briefly the manner in which the well was plugged)

8 5/8" at 185' circulated with cement - 5 1/2" at 3784 -perforated
at 3770'.

Filled with sand to 3760', set 4 sax cement with dump bailer,
pulled 2520' 5 1/2" - mud to 180', set rock and 15 sax cement, mud
to 35', set rock and 10 sax cement to bottom cellar.

PLUGGING
FILE SEC 18 T 10 R 19
BOOK PAGE 39 LINE 29

REC'D
3-2-56
CONCERN
WICHITA

Edson Peck
District Conservation Agent
Date 2-29-56