

15-163-01950-0000

Form CP-3
Rev. 6-4-68

KANSAS

PL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
5-16-73
MAY 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Russ Casing Pulling, Inc.

Complete Address Box 1082 Great Bend, Kansas 67530

Lease Name Lillian Scoggins Well No. 1

Location NE NW SW
330' FNL & 990' FWL of SW/4 Sec. 18 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3778'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor _____ Co. Tools _____

Address _____ License No. _____

Operation Completed: Hour 2:30 P Day 15 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 3778' 8 5/8 csg set at 1540' cwc 850 sk.

5 1/2 csg set at 3772' cw 300 sk cmt.

5 1/2 csg FBTD 3731' & perf. (3500-3510)

Filled 5 1/2 csg W/sd (3450-3731) Dumped 5 sk cmt W/dump bailer. (3415-3450)

Cutoff and recovered 2600' of 5 1/2 csg.

Set 8 5/8 wood plug at 735' -rock & sand (720-735) Dumped 3 yds readymix cmt (500-720)

Mud to 225' -rock & sand (210-225) dumped 3 yds readymix cmt 210' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Messing
Well Plugging Supervisor

DATE 5/16/73
INV. NO. 9355-W