

15-163-01954-0000

Form CP-3
Rev. 6-4-68

KANSAS

PL
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
5-16-73
MAY 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Russ Casing Pulling, Inc.
Complete Address Box 1082 Great Bend, Kansas 67530
Lease Name Lillian Scroggins Well No. 5
Location *CSW NW SW* 990' FNL & 330' FWL of SW/4 Sec. 18 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3778'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Co. Tools.
Address License No.
Operation Completed: Hour 3 P Day 15 Month 5 Year 1973

The above well was plugged as follows:

Total Depth: 3778' 8 5/8 csg set at 1635' cwc 650 sk.
5 1/2 csg set at 3773' cw 250 sk cmt.
5 1/2 csg PBSD 3702' with perf. (3244-3249)
Filled 5 1/2 csg W/sd (3200-3702') Dumped 5 sk cmt with dump bailer. (3165-3200)
Cutoff and recovered 2624' of 5 1/2 csg.
Set 8 5/8 wood plug at 735' -rock & sand (720-735) Dumped 3 yds readymix cmt. (500-720)
Mud to 225' -set rock & sand (210-225) Dumped 3 yds readymix cmt from 210' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *Eric F. Maxey*
Well Plugging Supervisor

INVOICED
DATE 5/16/73
INV. NO. 7356-W