

15-163-01957-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
5-16-73
MAY 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Russ Casing Pulling, Inc.

Complete Address Box 1082 Great Bend, Kansas 67530

Lease Name Lillian Scroggins Well No. 8

Location C NW NW SW 330' FNL. & 330' FWL of SW/4 Sec. 18 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3795'

Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Cb. Tools

Address _____ License No. _____

Operation Completed: Hour 3 P Day 15 Month 5 Year 1973

The above well was plugged as follows:

Total Depth 3795' 8 5/8 csg set at 1637' cwc 700 sax.

5 1/2 csg set at 3789' cw 200 sx cem.

5 1/2 csg PBTD 3727' and perf. (3491-3499)

Set 5 1/2 wood plug at 3450' -poured 10' sand -dumped 5 sk cmt W/dump bailer. (3415-3450)

Cutoff and recovered 2800' of 5 1/2 csg.

Set 8 5/8 wood plug at 735' -rock & sand (720-725) Dumped 3 yds readymix cmt. (500-720)

Mud to 225' -rock & sand (210-225) Dumped 3 yds readymix cmt 210' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Len F. Messing
Well Plugging Supervisor

DATE 5/16/73

INV. NO. 7357-W