

15-163-01969-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
5-16-73
MAY 16 1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Russ Casing Pulling, Inc.
Complete Address Box 1082 Great Bend, Kansas 67530
Lease Name Lillian Scroggins Well No. 10
Location 990' FNL & 990' FWL of SW/4 Sec. 18 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3835'
Abandoned Oil Well Gas Well Input Well SWD Well D & A
Other well as hereafter indicated _____
Plugging Contractor Co. Tools
Address _____ License No. _____

Operation Completed: Hour 2:30 P Day 15 Month 5 Year 1973

The above well was plugged as follows:

- Total Depth 3835' 8 5/8 csg set at 1640' cwc 650 sax.
- 5 1/2 csg set at 3835' cw 300 sk cmt.
- 5 1/2 csg PBD 3696' with top perf. (3607)
- Filled 5 1/2 csg W/sd (3550-3696) Dumped 5 sk cmt W/dump bailer. (3515-3550)
- Cutoff and recovered 2300' Of 5 1/2 csg.
- Set 8 5/8 wood plug at 735' -rock & and (720-735) Dumped 3 yds readymix cmt (500-720)
- Mud to 225' -set rock & sand (210-225) Dumped 3 yds readymix cmt 210' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 5/16/73
INV. NO. 7358-W

Signed: Leo F. Massey
Well Plugging Supervisor