

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
3-2-70
MAR 2 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Al Tipton

Complete Address Box 99 Iola, Kansas

Lease Name Berland "A" Well No. 10

Location SW SW NW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3787

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 10A Day 25 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3787 8 5/8 csg set at 1623' cwc 800'

5 1/2 csg set at 3785' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3770-3787) dumped 5 sk cmt W/dump bailer. (3730-3770)

Cutoff and recovered 3017' of 5 1/2 csg.

Mud to 700' - 3yds readymix (500-700) mud (200-500) 3yds readymix (0-200)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: [Signature]
Well Plugging Supervisor

DATE 3/2/70

INV. NO. 1517-W