

KANSAS

al

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
9-4-70
SEP 4 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Al Tipton

Complete Address P. O. Box 99 Iola, Kansas 66749

Lease Name H. Berland Well No. 4

Location NE NE SW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3807

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Co., Inc.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 3 P Day 3 Month 9 Year 1970

The above well was plugged as follows:

Total Depth 3807' 8 5/8 csg set at 1625' cwc 800 sk.

5 1/2 csg set at 3404' cw 100 sk cmt.

Set 5 1/2 wood plug at 3400' - poured sd and dumped 5 sk cmt W/dump bailer. (3350-3400)

Cutoff and recovered 3110' of 5 1/2 csg.

Filled 8 5/8 csg W/mud to 750' - set rock and dumped 3 sk RMC. (500-750)

Filled with mud (240-500) set rock and dumped 3 yds RMC. (0-240)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Bo J. Massey
Well Plugging Supervisor

DATE 9-4-70

INV. NO. 2480-W