

15-163-02680-0000

Form CP-3
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-10-72
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Al Tiptom

Complete Address Box 157 Hays, Kansas 67601

Lease Name H. Berland Well No. 3 - (SWD)

Location NE SW SW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 4292'

Abandoned Oil Well Gas Well Input Well SWD Well XX D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas 67530 License No. 670

Operation Completed: Hour 1:15 P Day 8 Month 1 Year 1972

The above well was plugged as follows:

Total Depth 4292' 8 5/8 csg set at 1617' cwc 800 sk.

5 1/2 csg set at 3804' cw 50 sk cmt.

4 1/2 liner set (3746-4012) cw 25 sk cmt.

Set wood plug (5 1/2') at 3750' -poured 30' sd -dumped 5 sk cmt W/dump bailer. (36750-3750)

Cutoff and recovered 2200' of 5 1/2 csg.

Mud to 735' -set rock & sand bridge to 720' -dumped 3 yds readymix cmt (720-720)

Mud to 235' -set rock & sand bridge (210-235) Dumped 3 yds readymix cmt 210 to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE 1-13-72

INV. NO. 4986-W