

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1-22-70  
JAN 22 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Al Tipton

Complete Address Box 99 Iola, Kansas 66749

Lease Name Berland Well No. 2

Location SW NE SW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3785

Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated       

Plugging Contractor Forbes Casing Pulling Co.

Address Box 221 Great Bend, Kansas License No. 637

Operation Completed: Hour 2:45P Day 20 Month 1 Year 1970

The above well was plugged as follows:

Total Depth 3785' 8 5/8 csg set at 1608' cwc

5 1/2 csg 3783' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3750-3785) Dumped 5 sk cmt W/dump bailer. (3710-3750)

Cutoff and recovered 2900' of 5 1/2 csg.

Mud to 720' set rock bridge (700-720) Dumped 20 sk cmt. (640-700)

Mud to 250' set rock bridge (230-250) Dumped 20 sk cmt. (170-230)

Mud to 40' set rock bridge (30-40) Filled to base of cellar W/10 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 1/22/70  
NO. 1291-W

Signed: Leo J. Messing  
Well Plugging Supervisor