

15-163-01960-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-10-71
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Al Tipton
Complete Address Box 157 Hays, Kansas 67601
Lease Name H. Berland Well No. 5
Location SW SE NW Sec. 19 Twp. 10 Rge. (E) (W) 19W
County Rooks Total Depth 3796'
Abandoned Oil Well XX Gas Well _____ Input Well _____ SWD Well _____ D & A _____
Other well as hereafter indicated _____
Plugging Contractor Forbes Casing Pulling
Address Box 698 Great Bend, Kansas License No. 670
Operation Completed: Hour 4 P Day 7 Month 12 ~~1971~~ Year 1971

The above well was plugged as follows:

Total Depth 3796' 8 5/8 csg set at 1621' cwc 800 sk.
5 1/2 csg set at 3792' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (3750-3796) Dumped 5 sk cmt W/dump bailer. (3710-3750)
Cutoff and recovered 2600' of 5 1/2 csg.
Set rock & cmt bridge (720-735) Dumped 3 yds readymix cmt (500-720)
Mud to 235' -set rock & sd bridge (210-235) Dumped 3 yds readymix cmt (0-210)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Ray F. Murray
Well Plugging Supervisor

DATE 12/10/71
INV. NO. 4796-W