

15-163-01962-0000

Form CP-3
Rev. 6-4-68

KANSAS

W

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-10-71
DEC 10 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Al Tipton

Complete Address P. O. Box 157 Hays, Kansas 67601

Lease Name H. Berland Well No. 7

Location SW SE SW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3808'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 5:30 P Day 7 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3808' 8 5/8 csg set at 1618' cwc 800 sk.

5 1/2 csg set at 3806' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3790-3808) Dumped 5 sk cmt W/dump bailer. (3755-3790)

Cutoff and recovered 3100' of 5 1/2 csg.

Set ock & sd bridge (720-735) Dumped 3 yds readymix cmt (500-720)

Mud to 225' set rock & sd bridge (220-225) Dumped 3 yds readymix cmt (0-220)

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/10/71
INV. NO. 4499-W

Signed: Leo J. Massey
Well Plugging Supervisor