


KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
12-17-71  
DEC 17 1971  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Al Tipton  
Complete Address Box 157 Hays, Kansas 67601  
Lease Name H. Berland "A" Well No. 13  
Location NE SE NW Sec. 19 Twp. 10 Rge. (E) (W) 19  
County Rooks Total Depth 3801'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering, Inc.  
Address Box 698 Great Bend, Kansas License No. 670  
Operation Completed: Hour 4 P Day 13 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3801' 8 5/8 csg set at 1631' cwc 800 sk.  
5 1/2 csg set at 3797' cw 100 sk cmt.  
Filled 5 1/2 csg W/sd (3770-3801) Dumped 5 sk cmt W/dump bailer. (3735-3770)  
Cutoff and recovered 2570' of 5 1/2 csg.  
Mud to 735' -set rock bridge (720-735) Dumped 3 yds readymix cmt (510-720)  
Mud to 225' -set rock bridge (215-225) Dumped 3 yds readymix cmt (0-215)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Eric F. Messer  
Well Plugging Supervisor

DATE 12/17/71  
NO. 4826-W