

15-163-01144-0000

Form CP-3
Rev. 6-4-68

KANSAS

JL
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
1-10-72
JAN 10 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Al Tipton

Complete Address Box 157 Hays, Kansas 67601

Lease Name H. Berland "A" Well No. 15

Location NW NW NW Sec. 19 Twp. 10 Rge. (E) (W) 19

County Rooks Total Depth 3766'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Rockhold Engineering, Inc.

Address Box 698 Great Bend, Kansas License No. 670

Operation Completed: Hour 12:30 P Day 8^o Month 1 Year 1972

The above well was plugged as follows:

Total Depth 3766' 8 5/8 csg set at 1618' cwc 800 sk.

5 1/2 csg set at 3761' cw 100 sk cmt.

Filled 5 1/2 csg W/sd (3730-3766) dumped 5 sk cmt W/dump bailer. (3690-3730)

Cutoff and recovered 2880' of 5 1/2 csg.

Set rock & sand bridge (720-735) Dumped 3 yds readymix cmt (510-720)

Mud to 225' -set rock & sand bridge (210-225) Dumped 3 yds readymix cmt. (0-210)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Murray
Well Plugging Supervisor

DATE 1-13-72

INV. NO. 4985-W