

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION  
2-5-70  
FEB 5 1970  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Al Tipton  
Complete Address Box 99 Iola, Kansas 66749  
Lease Name Berland "A" Well No. 8  
Location NE SW NW Sec. 19 Twp. 10 Rge. (E) (W) 19  
County Rooks Total Depth 3791  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Southwest Casing Pulling  
Address Box 364 Great Bend, Kansas License No. 399  
Operation Completed: Hour 12N Day 3 Month 2 Year 1970

The above well was plugged as follows:

Total Depth 3791' 8 5/8 csg set at 1618' cwc 800 sk.  
5 1/2 csg set at 3780' cw 100 sk cmt.  
5 1/2 csg PBSD 3495' and perf. (3475-3478)  
Filled 5 1/2 csg W/sd (3460-3495) Dumped 5 sk cmt W/dump bailer. (3420-3460)  
Cutoff and recovered 3205' of 5 1/2 csg.  
Mud to 714' set wood plug and rock (700-714)  
Set 65 sk cmt plug (500-700) Filled with mud (50-500) set wood plug and rock (40-50)  
Filled with 10 sk cmt (40 to base of cellar).

I hereby certify that the above well was plugged as herein stated.

Signed: Ken F. Manney  
Well Plugging Supervisor

INVOICED  
DATE - 2/6/70  
INV. NO. 1369-U