

15-163-01961-0000

Form CP-3
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
12-17-71
DEC 17 1971
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Al Tipton
Complete Address Box 157 Hays, Kansas 67601
Lease Name H. Berland "A" Well No. 6
Location NE NW SW Sec. 19 Twp. 10 Rge. (E) (W) 19
County Rooks Total Depth 3782'
Abandoned Oil Well XX Gas Well Input Well SWD Well D & A
Other well as hereafter indicated
Plugging Contractor Rockhold Engineering, Inc.
Address Box 698 Great Bend, Kansas 67530 License No. 670
Operation Completed: Hour 3 P Day 13 Month 12 Year 1971

The above well was plugged as follows:

Total Depth 3782' 8 5/8 csg set at 1609' cwc 800 sk.
5 1/2 csg set at 3777' cw 100 sk cmt.
Filled 5 1/2 csg W/sd (3750-3782) Dumped 5 sk cmt W/dump bailer. (3715-3750)
Cutoff and recovered 3135' of 5 1/2 csg.
Mud to 735' -set rock bridge (720-735) Dumped 3 yds readymix cmt. (510-720)
Mud to 220' -set rock bridge (210-220) Dumped 3 yds ready mix cmt (0-210)

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Messup
Well Plugging Supervisor

INVOICED
DATE 12/17/71
INV. NO. 4825-W