

DISTRICT CONSERVATION AGENT'S REPORT

R

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. _____

LOCATION NE NE NE

SEC. 19 TWP. 10 RGE. 19W

Dry Hole x Abandoned Oil Well _____ Abandoned Gas Well _____

I have today completed supervision of plugging of:

Well No. 1 Lease Berland

Operator C & G Drg Co Address Wichita, Kans

Field _____ County Rooks

Total Depth 3784 Feet.

(Describe briefly the manner in which the well was plugged)

8 5/8" at 190' circulated with cement - 5 1/2" at 3778' with
100 sax cement behind.

Filled with chat to 3760', set 4 sax cement with dump bailer,
pulled 2909' 5 1/2", filled with mud to 190', set rock bridge
and 15 sax cement, mud to 35', set rock and 10 sax cement
to bottom cellar.

RECEIVED
STATE CORPORATION COMMISSION
6-4-52
JUN 4 - 1952
CONSERVATION DIVISION
Wichita, Kansas

[Signature]
District Conservation Agent
Date 6-1-52

PLUGGING
FILE SEC 19T-10R-19W
BOOK PAGE 21 LINE 9