

15-163-20139-0000

Form CP-3  
Rev. 6-26-62

*al*

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
6-22-68  
OCT 22 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name John C. Graves Et al

Complete Address: 505 Union Center Wichita, Kansas

Lease Name Berland Well No. 1

Location N/2 N/2 NE Sec. 19 Twp. 10 Rge. 19 (E) XX (W) XX

County Rooks Total Depth 3857

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 6:30A Day 20 Month 10 Year 1968

The Above well was plugged as follows:

RTD 3857' 8 5/8 csg set at 217' cwc Amt Mat 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sc cmt

thru Drill pipe. Heavy mud to 210' set cementing plug and displaced 20 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 10/11/68

INV. NO. 8676-11

Signed: *Paul F. Massey*  
Well Plugging Supervisor