

15-163-01974-0000

Form CP-3  
Rev. 6-4-68

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
11-22-71  
NOV 22 1971  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Al Tipton  
Complete Address Box 157 Hays, Kansas  
Lease Name H. Berland "A" Well No. 11  
Location SW NW NW Sec. 19 Twp. 10 Rge. (E) (W) 19  
County Rooks Total Depth 3776'  
Abandoned Oil Well XX Gas Well        Input Well        SWD Well        D & A         
Other well as hereafter indicated         
Plugging Contractor Rockhold Engineering, Inc.  
Address Box 221 Great Bend, Kansas License No. 637  
Operation Completed: Hour 3 P Day 20 Month 11 Year 1971

The above well was plugged as follows:

Total Depth 3776' 8 5/8 csg set at 1618' cwc 800 sk.  
5 1/2 csg set at 3772' cw 100 sk cmt.  
Filled 5 1/2 csg W/sd (3750-3776) Dumped 5 sk cmt W/dump bailer. (3710-3750)  
Cutoff and recovered 2350' of 5 1/2 csg.  
Mud to 720' set rock & cmt plug (700-720) Dumped 3yds readymix cmt (500-700)  
Mud to 220' set rock & sd bridge (210-220) Dumped 3 yds readymix cmt (0-210)

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Wessner  
Well Plugging Supervisor

DATE 11-29-71  
INV. NO. 4685-W