

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-163-22,098-0000

LEASE NAME Berland

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

4950 Ft. from S Section Line

630 Ft. from E Section Line

SEC. 19 TWP. 10 RGE. 19 ~~KCC~~ (W)

COUNTY Rooks

Date Well Completed 9/9/83

Plugging Commenced 4/20/88

Plugging Completed _____

LEASE OPERATOR Bowman Oil Company

ADDRESS Box 17 Codell, Kansas 67630

PHONE# (913) 434-2304 OPERATORS LICENSE NO. 6931

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 3/31/88 (date)

by Dennis Hamel (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3776 Bottom 3780 T.D. 3793

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Arbuckle	Oil & Water	3776	3793	8 5/8	271	None
				5 1/2	3823	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.
271' of 8 5/8 cemented with 200 sx, 5 1/2" set at 3823' with 115 sx, two-stage from 1639' to surface with 375 sx. Arbuckle 3784-93 squeezed with 75 sx. 5 1/2" filled from surface to 3784' with 150 sx B-J lite cement with cello-flake.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor B-J Titan Service Company License No. _____

Address P. O. Box 200416 Houston, Texas 77216 (Job invoice RL4068)

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Bowman Oil Company

STATE OF Kansas COUNTY OF Rooks, ss.

Louis D. Bowman

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Louis D. Bowman

(Address) Box 17

DESCRIBED AND SWORN TO before me this 26 day of August, 19 88

Vesta J. Russell
Notary Public

CONSERVATION DIVISION
State of Kansas

Commission Expires: July 17, 1992

