

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD

K.A.R.-82-3-117

API NUMBER 15-163-23002
LEASE NAME HENRY BERLAND

TYPE OR PRINT

WELL NUMBER 3-19

NOTICE: Fill out completely 1090 Ft. from S Section Line
and return to Cons. Div. 330 Ft. from E Section Line
office within 30 days

LEASE OPERATOR Murfin Drilling Co., Inc.
ADDRESS 250 N. Water, Suite 300; Wichita, KS 67202
PHONE # (316) 267-3241 OPERATORS LICENSE NO. 30606

SEC 19 TWP. 10S RGE. 19W (E) or (W)
COUNTY ROOKS
Date Well Completed 7/11/88

Character of Well OIL (Oil, Gas, D&A, SWD, Input, Water Supply Well) Plugging commenced 4/11/03
Plugging Completed 4/11/03

The plugging proposal was approved on 4/11/03 (date)
by Pat Staab w/KCC Hays, KS. (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? no

Producing Formation Arbuckle Depth to Top 3772.5 Bottom 3775.5 TD 3850

Show depth and thickness of all water oil and gas formations.

OIL, GAS, OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		surface	231	8 5/8	231	0
		production	3849	5 1/2"	3849	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set.

Plugged well as follows: Tied onto 8 5/8". Pressured to 500# & held. Tied onto 5 1/2" csg. Pumped 35 sxs 60-40 poz 10% gel, 250# hulls, 19 sxs gel 250# hulls, 135 sxs 60-40 poz 10% gel, 1000# max press 900#ISIP. Well P/A. Witnessed and approved by Pat Staab w/ KCC Hays, KS.

Name of Plugging Contractor Murfin Drilling Company, Inc. License No. 30606
Address 250 N. Water, Suite 300; Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Murfin Drilling Company, Inc.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

Tom W. Nichols, Production Manager (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, state and contents of the matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

RECEIVED
4-25-03
APR 25 2003


(Signature) Tom W. Nichols
(Address) Wichita, KS

KCC WICHITA

SUBSCRIBED AND SWORN TO before me this 14th day of April, 2003

Notary Public - Barbara J. Dodson Barbara J. Dodson

My Commission Expires: 12/16/03 Form CP-4 Revised 05-88



Bm

ALLIED CEMENTING CO., INC. 13415

15-163-23002-0000

REMIT TO P.O. BOX 31
RUSSELL, KANSAS 67665

SERVICE POINT: Russell

DATE <u>4-11-03</u>	SEC. <u>19</u>	TWP. <u>10</u>	RANGE <u>19</u>	CALLED OUT	ON LOCATION <u>8:30 AM</u>	JOB START	JOB FINISH <u>9:00 AM</u>
LEASE <u>Beeland</u>		WELL # <u>319</u>		LOCATION <u>Zurich 2W42S W1W</u>		COUNTY <u>Rooks</u>	STATE <u>Ks</u>

OLD NEW (Circle one)

CONTRACTOR _____ OWNER _____

TYPE OF JOB Plug

HOLE SIZE _____ T.D. _____

CASING SIZE 5 1/2 DEPTH _____

TUBING SIZE _____ DEPTH _____

DRILL PIPE _____ DEPTH _____

TOOL _____ DEPTH _____

PRES. MAX _____ MINIMUM _____

MEAS. LINE _____ SHOE JOINT _____

CEMENT LEFT IN CSG. _____

PERFS. _____

DISPLACEMENT _____

CEMENT AMOUNT ORDERED

185 lbs 60/40-10
19 lb 60 50# Hulls Used 120 lbs

COMMON	<u>102</u>	@	<u>7.15</u>	<u>729.30</u>
POZMIX	<u>68</u>	@	<u>3.80</u>	<u>258.40</u>
GEL	<u>31</u>	@	<u>10.00</u>	<u>310.00</u>
CHLORIDE		@		
<u>Hulls</u>	<u>5</u>	@	<u>18.00</u>	<u>90.00</u>
		@		
		@		
		@		
		@		
HANDLING	<u>185</u>	@	<u>.45</u>	<u>212.75</u>
MILEAGE	<u>58/SK</u>	@	<u>1.15</u>	<u>351.90</u>
TOTAL				<u>1951.95</u>

EQUIPMENT

PUMP TRUCK CEMENTER Bill

HELPER PAJ

BULK TRUCK DRIVER Shane

DRIVER _____

REMARKS:

Pump down 5 1/2" of 350# of
1250# Hulls Follow w/ 19 lb 60
w/ 250# Hulls Follow w/ 135# Cement
may 1000# 700# SHUT IN

Ann 50# 50# Shot IN

SERVICE

DEPTH OF JOB	_____			
PUMP TRUCK CHARGE	_____		<u>475.00</u>	
EXTRA FOOTAGE	_____	@		
MILEAGE	<u>38</u>	@	<u>3.50</u>	
PLUG	_____	@		
		@		
TOTAL				<u>608.00</u>

CHARGE TO: MUFFIN

STREET _____

CITY _____ STATE _____ ZIP _____

FLOAT EQUIPMENT

_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____
_____	@	_____

To Allied Cementing Co., Inc.
You are hereby requested to rent cementing equipment and furnish cementer and helper to assist owner or contractor to do work as is listed. The above work was done to satisfaction and supervision of owner agent or contractor. I have read & understand the "TERMS AND CONDITIONS" listed on the reverse side.

RECEIVED
APR 25 2003
KCC WIOHITA

TOTAL	_____
TAX	_____
TOTAL CHARGE	_____
DISCOUNT	_____ IF PAID IN 30 DAYS

SIGNATURE John Gustave

PRINTED NAME _____