

State of Kansas



15-167-20279-00-00

ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GIAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 1-20-1969
 JAN 20 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company, Inc. has this date requested permission to plug the following described well:

Mr. Robert J. Shields guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Building, Russell, Kansas 67665

Lease Name: Davis "A" Well No. # 1

Location: NE SW SE Sec. 34 Twp. 12 Rge. 15 (E) (W) W

County: Russell Total Depth 2935 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" 250' Cwc.

Circulated hole with heavy mud to 500', set plug, & displaced 50 sax

cement thru drill pipe. Mud to 240' & displaced 25 sax cement thru drill

pipe. Mud to 40', 1/2 sax hulls, plug, & displaced 10 sax cement with

Halliburton Cementing Company's pump truck, cementing to base of cellar.

Very truly yours,

Don Truman
 Conservation Division Agent