

State of Kansas



15-167-2004-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-28-1967
FEB 28 1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Ed Weiler of Shields Drilling Company, Inc. this
date requested permission to plug the following described well:

Mr. Robert J. Shields guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Inc.

Complete Address: Shields Bldg., Russell, Kansas

Lease Name: Holland "C" Well No. # 1

Location: NW SW SW Sec. 35 Twp. 12 Rge. 15 (E)(W)W

County Russell Total Depth 3295 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8" 272' Cwc.

Circulated hole with heavy mud to 265', set plug with 1/4 sax hulls,

& displaced 25 sax cement thru drill pipe. Mud to 40', 1/2 sax

hulls, plug, & displaced 10 sax cement, cementing to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent