



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

4-4-1977
M.C. [unclear]

Conservation Division
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Branum of Emphasis Drlg. has this date requested permission to plug the following described well:

Mr. Branum guarantees payment of the plugging fee.

Operator's full Name: Paramount Petro.

Complete Address: 357 Lulu, Wichita, Ks.

Lease Name: Chrisler Well No. 2

Location: NE NW NE Sec. 9 Twp. 12 Rge. (E)(W) 16

County: Ellis Total Depth 3405' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Branum was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 50 sk cmt plug at 500' thru drill

pipe. Heavy mud to 185' set 25 sk cmt plug thru drill pipe. Heavy

mud to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

R. C. Massey
Conservation Division Agent