



15-051-20598-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-24-1970
MAR 24 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Draper of Dreiling Oil Co. has this
date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company

Complete Address: Victoria, Kansas

Lease Name: Dickinson S Well No. 5

Location: SE SE SW Sec. 10 Twp. 12 Rge. (E)(W) 16

County: Ellis Total Depth 3370 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Draper was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 480' and displace

50 sk cmt thru drill pipe. Heavy mud to 260' set cementing plug and

displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing

plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent