



Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION 1031752  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING RECORD**  
K.A.R. 82-3-117

Form CP-4  
March 2009  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

OPERATOR: License #: 4058  
Name: American Warrior, Inc.  
Address 1: PO Box 399  
Address 2: \_\_\_\_\_  
City: GARDEN CITY State: KS Zip: 67846 + \_\_\_\_\_  
Contact Person: Scott Corsair  
Phone: (785) 398-2270  
Type of Well: (Check one)  Oil Well  Gas Well  OG  D&A  Cathodic  
 Water Supply Well  Other: \_\_\_\_\_  SWD Permit #: \_\_\_\_\_  
 ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No  
Producing Formation(s): List All (If needed attach another sheet)  
Mississippian Depth to Top: 4322 Bottom: 4330 T.D. 4330  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_  
\_\_\_\_\_ Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API No. 15-135-21001-00-00  
Spot Description: \_\_\_\_\_  
E2 W2 NE NW Sec. 34 Twp. 20 S. R. 22  East  West  
660 Feet from  North /  South Line of Section  
1,830 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Ness  
Lease Name: MCFADDEN Well #: 3  
Date Well Completed: 05/19/1975  
The plugging proposal was approved on: 09/17/2009 (Date)  
by: Mike Maier (KCC District Agent's Name)  
Plugging Commenced: 09/17/2009  
Plugging Completed: 09/17/2009

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
Mississippian	oil/water	Surface	8.625	417	0
		Production	5.5	4323	0

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Swift Services mixed and pumped 40 sacks of cement 60/40 poz, 4 % gel with 150# hulls, spotted balanced plug through 2 3/8ths tubing @ 4300'. Pull tubing to 1450' and set 50 sack hot plug of standard cement with 3% cc. Pull tubing to 950' and circulate 75 sacks of 60/40 poz, 4% gel to surface. PULL tubing out and top of with 10 sacks of 60/40 poz, 4% gel. Well plugged.

Plugging Contractor License #: 32382 Name: Swift Services, Inc.  
Address 1: PO BOX 466 Address 2: N HWY 283  
City: NESS CITY State: KS Zip: 67560 + 0466  
Phone: (785) 798-2300  
Name of Party Responsible for Plugging Fees: American Warrior  
State of Kansas County, Ness, ss.  
Scott Corsair  Employee of Operator or  Operator on above-described well,  
(Print Name)

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Submitted Electronically

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

RECEIVED  
OCT 05 2009  
KCC WICHITA