

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-051-23528-00-01

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Grady Bolding Corporation

ADDRESS Box 244, Great Bend, Ks. 67530

PHONE # (316) 793-8628 OPERATORS LICENSE NO. 7383

Character of Well Oil
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Six

Is ACO-1 filed? If not, is well log attached? With application

Producing formation Depth to top bottom T.D. 3510'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	216'	None
				4-1/2"	3471'	2,211.03'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Dumped sand to 3075' and 4 sacks cement. Shot casing at 2700', 2500 and 2250'. Pulled 52 joints of 4-1/2" casing. Squeezed well with 4 sacks hulls, 10 sacks gel, 1/2 sack hulls, 30 sacks cement, 12 sacks gel, 1/2 sack hulls, released plug and pumped 140 sacks 60/40 pozmix cement with 6% added gel and 3% calcium chloride. Maximum pressure was 700 psi and shutin 700 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111
Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well as filed that the same are true and
correct, so help me God.

(Signature)

James W. Rockhold
(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 9th day of September, 1985



IONA M. LEATHERMAN
Barton County, Kansas
My Appt. Exp. 7/26/82

My Commission expires:

RECEIVED
STATE OF KANSAS NOTARY PUBLIC
SEP 10 1985
Iona M. Leatherman

SEP 10 1985

Form CP-4

CONSERVATION DIVISION