


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

15-051-19238-00-00
WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

ELLIS County. Sec. 10 Twp. 12S Rge. 16W (E) (W)

Location as "NE/CNW/SW" or footage from lines. NE NE NW

Lease Owner K & E DRILLING, INC.

Lease Name DICKINSON Well No. 1

Office Address 719 Union Center

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed October 28th, 1959 19

Application for plugging filed October 28th, 1959 19

Application for plugging approved October 28th, 1959 19

Plugging commenced October 28th, 1959 19

Plugging completed October 28th, 1959 19

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3379' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	253'	--

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Fill with heavy mud to 450' set plug with 20 sx cement thru drill pipe. Fill with heavy mud to 240' set plug with 20 sx cement thru drill pipe. Fill with heavy mud to 40' set solid bridge with 1/3 sx hulls and 10 sx cement to base of c&h. Job Complete 10-28-59.

RECEIVED
STATE CORP. COM. DIV.
11-6-1959
NOV 6 1959

CONSERVATION DIVISION

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.

Address 719 Union Center, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Dale Silcott (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott, of K & E DRILLING, INC.
719 Union Center, Wichita 2, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 5th day of November, 1959

My commission expires August 11th, 1962.

Patricia M. Edwards, Notary Public.



15-051-19238-00-00
DRILLER'S WELL LOG

OPERATOR: **K & E DRILLING, INC.**
 719 Union Center
 Wichita 2, Kansas

WELL NAME: **#1 DICKINSON**
 LOCATION: **NE NE NW**
Section 10-12S-16W
ELLIS COUNTY, KANSAS

CONTRACTOR: **K&E DRILLING, INC.**
 719 UNION CENTER BLDG.
 WICHITA, KANSAS

COMMENCED: **October 20th, 1959**
 COMPLETED: **October 28th, 1959**

CASING RECORD: **8-5/8" @ 253' (160 sx cmt)**

ELEVATION: **1794' KB**

ROTARY TOTAL DEPTH: **3379'**

PRODUCTION: **D & A**

FORMATION RECORD

Depths shown indicate bottom of formations encountered.

Surface Soil & Clay	25
Post Rock	70
Shale	252
Shale	330
Sand & Shale	600
Red Bed	890
Red Bed	955
Anhydriye	990
Shale & Shells	1690
Lime & Shale	2425
Shale & Lime	2675
Lime & Shale	2815
Lime	2890
Lime & Shale	2980
Lime	3230
Lime & Shale	3325
Lime	3379
Total Depth	3379'

11-6-1959

CERTIFICATION

State of KANSAS }
 County of SEDGWICK } ss:

I, Dale Silcott, of K&E DRILLING, INC., upon oath state that the above and foregoing is a true and correct copy of the Driller's Log of the above named well.

Dale Silcott
 Dale Silcott

Subscribed and sworn to before me this 5th day of November, 19 59.

Patricia M. Edwards
 Patricia M. Edwards, Notary Public.

My Commission expires: August 11th, 1962.

