

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20268-00-01
Spot: SESWNW Sec/Twnshp/Rge: 29-31S-21W
3240 feet from S Section Line, 4555 feet from E Section Line
Lease Name: MOORE Well #: 8
County: CLARK Total Vertical Depth: 4895 feet

Operator License No.: 4058
Op Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	633		WITH 300 SX CMT
PROD	5.5	4761	2997	WITH 250 SX CMT 159.09

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 08/06/2009 10:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: PUMP 250# HULLS & 25 SX CMT. PLUG AT 1080' LOAD WITH GEL WATER & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 280' WITH 30 SX CMT. PLUG AT 40' WITH 10 SX CMT

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2009 11:00 AM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

DETERMINED HOLE IN SURFACE CASING AT APPROXIMATELY 145'. 1ST PLUG PUMP 300#HULLS & 25 SX CMT TO 4400'. 2ND PLUG PULL CASING TO 1080'. ATTEMPTED TO LOAD HOLE WITH MUD, PUMPED 50 SX CMT. NO RETURNS. 3RD PLUG PULL CASING TO 660'. PUMPED 50 SX CMT. NO RETURNS. 4TH PLUG TAGGED TOC @ 528'. PULLED CASING TO 280'. PUMPED 30 SX CMT. NO RETURNS SDFN. 5TH PLUG TAGGED TOC @ 254'. F.L. @ 145'. PUMPED 10 BBL MUD & 40 SX CMT @ 155'. 6TH PLUG TAGGED TOC @ 25'. FILLED CASING WITH 6 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4420	4684		

INVOICED
9-29-09
2010060282

RECEIVED
AUG 19 2009

Remarks: USED COMMON CEMENT BY SARGENTS.

KCC WICHITA

Plugged through: CSG

District: 01

Signed

Jerry W. Stapleton
PIRT II (TECHNICIAN)

RECEIVED
AUG 12 2009
KCC DODGE CITY