

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-08688-00-00
Spot: SENESE Sec/Twnshp/Rge: 11-9S-17W
1650 feet from S Section Line, 330 feet from E Section Line
Lease Name: WESTHUSIN Well #: 10
County: ROOKS Total Vertical Depth: 3434 feet

Operator License No.: 5363
Op Name: BEREXCO, INC.
Address: PO BOX 20380
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	256	0	w/225 sxs cmt
PROD	5.5	3432	0	w/125 sxs cmt <u>111.61</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/13/2009 12:00 PM
Plug Co. License No.: 5363 Plug Co. Name: BEREXCO, INC.
Proposal Rcvd. from: CURT GABEL Company: BEREXCO, INC. Phone: (316) 265-3311

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel with 3% c.c. - 800# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2009 4:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Holes in casing from 501' to 784' and from 784' - 2506'.
Ran tubing to 3350' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 2450' - pumped 100 sxs cement with 300# hulls.
Pulled tubing to 2050' - pumped 150 sxs cement with 100# hulls - good circulation of cement.
Pulled tubing - tied onto 8 5/8" - pumped 60 sxs cement - shut in.
Pumped 35 sxs cement with 100# hulls down the 5 1/2" - full.

Perfs:

INVOICED
DATE: 9-29-09
INV. NO. 2010060285

RECEIVED
AUG 21 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed *Marvin Mills*
(TECHNICIAN)

em

AUG 14 2009

PM

C R A

#10 WESTHUSIN

11-9-17W
SE NE SE

Contr. SHOLOM DRLG ROOKS County

E 2029KB Comm. 6/13/63 Comp. 7/10/63 IP PMP 10 80+100 BWP,
(ARB 3432-34)


SMP Tops	Depth	Datum
ANH	1278	+751
HEEB	3104	-1075
TOR	3126	-1097
KC	3145	-1116
ARB	3430	-1401
RTD	3434	-1405

Casing

8" 256/225 sx:
5" 3432/125 sx:

DST 3039-65/1', 310' MW, + SCUM O,
BHP 881-727#/30", FP 76-153#:
DST 3184-3222/1', 210' WM, + SPECKS
O, BHP 153-153#/30", FP 76-78#:
DST 3297-3352/TOOL PLUGGED:
CO 3434 TD: BAIL 6 GOPH/6 HRS, 250
A, SWB 2 1/2 BO+6 BWP/2 HRS, POP:

WESTHUSIN



GEOL: BOB ARMSTRONG:

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS