

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-01452-00-00  
Spot: NWNENW Sec/Twnshp/Rge: 21-9S-21W  
4950 feet from S Section Line, 3630 feet from E Section Line  
Lease Name: ANDRESON B Well #: 1  
County: GRAHAM Total Vertical Depth: 3746 feet

Operator License No.: 7076  
Op Name: BLACK DIAMOND OIL, INC.  
Address: PO BOX 641  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	195	0	125 SX
L1	4.5	3203	0	25 SX
PROD	5.5	3743	0	125 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/13/2009 3:00 AM  
Plug Co. License No.: 33772 Plug Co. Name: GASCHLER PULLING SERVICE, INC.  
Proposal Rcvd. from: KENNETH VEHIGE Company: BLACK DIAMOND OIL, INC. Phone: (785) 625-5891

Proposed Plugging Method: Ordered 400 sxs 60/40 pozmix - 4% gel - 500# hulls.  
Superior perferd two hole shots at 2175' - 1725' - 800' 150'.  
Operator selected all cement plug.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/13/2009 8:20 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Gaschler Pulling Service RIH with tubing to 3000'.  
Allied rigged to tubing and pumped 150 sxs cement with 300# hulls.  
Pulled tubing to 1850'. Allied rigged to tubing and pumped 65 sxs cement with 200# hulls mixed into circulate cement to pit  
Pulled tubing. Allied rigged to 4 1/2" casing and pumped 15 sxs cement to circulate out 5 1/2" casing. Shut in 5 1/2" casing.  
Max. P.S.I. 450#. S.I.P. 450#.  
Rigged to 8 5/8" - pumped 60 sxs cement.  
Max. P.S.I. 50#. S.I.P. 50#.

Perfs:

Top	Bot	Thru	Comments
3743	3744		
3618	3624		
3566	3572		
3514	3520		
3472	3475		
3434	3437		

INVOICED  
9-29-09  
2010060287

RECEIVED  
AUG 21 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38532.

Plugged through: TBG

District: 04

Signed Pat Staab  
(TECHNICIAN)

CM

AUG 14 2009


*Pat*

7

Barnett Drlg Co et al # 1 . Andreson "B" 21-9-21  
 NW NE NW  
 Contr Barnett Drlg. Co. Graham County  
 F. 2214 Comm 3-29-47 Comp 5-2-47 IP 3000 BOPD DEPTH

Tops	Depth	Datum
ANHY	1704	
HEER	3400	
LANS	3439	
BSE K G	3662	
ARB	3742	
TD	3746	

Casing  
 8" 195 2700' OIH/4 hrs.  
 5" 3742 Acid 500



INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS