

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-19214-00-01  
Spot: NENENW Sec/Twnshp/Rge: 27-18S-10W  
4937 feet from S Section Line, 2809 feet from E Section Line  
Lease Name: HABIGER TWIN Well #: 5  
County: RICE Total Vertical Depth: 2700 feet

Operator License No.: 4707  
Op Name: BOXBERGER, CARL OIL, INC.  
Address: 3111 10TH ST STE 107 PO BOX 1604  
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	255		200 SX
PROD	5.5	2699		75 SX

87.75

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/27/2009 4:00 PM  
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.  
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE INC Phone: (620) 562-8088

Proposed Plugging Method: SEE BELOW

Plugging Proposal Received By: B. J. HOPE Witness Type: PARTIAL  
Date/Time Plugging Completed: 07/28/2009 10:00 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. PERFORATE AT 1200', 850', AND 300'. RUN TUBING TO 2660' AND PUMP 35 SX'S CEMENT WITH 200#'S COTTON HULLS. PULL TUBING TO 1200' AND PUMP 70 SX'S CEMENT WITH CALCIUM CHROLIDE. SHUT DOWN FOR DAY, TAG CEMENT TOP AT 820' ON 7-28-2009. PUMP 25 MORE SX'S CEMENT AT 820'. PULL TUBING TO 300' AND CIRCULATE CEMENT TO SURFACE. PULL TUBING OUT AND TOP OFF. CONNECT ON TO BACKSIDE OF 5.5" AND PUMP CEMENT UP TO 250#'S AND SHUT IN. USED 210 SX'S CEMENT.

Perfs:

Top	Bot	Thru	Comments
2655	2660		

RECEIVED  
AUG 20 2009  
KCC WICHITA

9-29-09  
2010060288

Remarks: 60-40 POZ, 4% GEL. LOG TECH OF KS TICKET #5786. COPELAND TICKET C-33037.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

*PKT*

*JK*