

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21168-00-00
Spot: SWNWNWSE Sec/Twnshp/Rge: 9-29S-6W
2085 feet from S Section Line, 2415 feet from E Section Line
Lease Name: BENSON-YEAGER Well #: 2
County: KINGMAN Total Vertical Depth: 4460 feet

Operator License No.: 5348
Op Name: CAMPBELL, ROBERT E.
Address: 260 N ROCK RD STE 110
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	218		225 SXS CMT
PROD	5.5	4458	2500	160 SXS CMT <u>144.95</u>

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/20/2009 8:00 AM
Plug Co. License No.: 5399 Plug Co. Name: AMERICAN ENERGIES CORPORATION
Proposal Rcvd. from: THAD STARR Company: _____ Phone: (316) 263-5785

Proposed Plugging Method: PER KCC RULES AND REGULATIONS.

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 05/21/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SANDED BACK TO 3800' TOPPED WITH 5 SXS OF CEMENT. SHOT OFF CASING AT 2500', PULLED ALL CASING AND RAN BACK IN WITH TUBING TO 968' SPOTTED 35 SXS OF COMMON CEMENT WITH 3% CC, TAGGED AT 800' PULLED CASING TO 552' SPOTTED 35 SXS OF COMMON CEMENT WITH 3% CC. PULLED TUBING TO 293' CIRCULATED TO SURFACE WITH 120 SXS OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4082	4088	CSG	
4072	4080		
4065	4070		

RECEIVED
AUG 18 2009
KCC WICHITA

9/29/09
2010060289

Remarks: ALLIED CEMENTING OUT OF MEDICINE LODGE, KS TICKET #34364

Plugged through: TBG

District: 02

Signed B. J. Hope
(TECHNICIAN)

1/54

PKO