

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-22005-00-00
Spot: NWSWNW Sec/Twnshp/Rge: 3-28S-5W
1650 feet from N Section Line, 330 feet from W Section Line
Lease Name: HILL Well #: 1-3
County: KINGMAN Total Vertical Depth: 4233 feet

Operator License No.: 5214
Op Name: LARIO OIL & GAS COMPANY
Address: 301 S MARKET ST
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	292		190 SX CMT
PROD	5.5	4010	2720	240 SX CMT <u>137.57</u>

Well Type: OG UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: BRAD SANDERS Company: LARIO OIL & GAS Phone: (785) 623-0017

Proposed Plugging Method: PER KCC RULES

Plugging Proposal Received By: VIRGIL CLOTHIER Witness Type: PARTIAL
Date/Time Plugging Completed: 07/31/2009 5:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

7/30/2009 SANDED BACK TO 3720' PLACED 5 SXS OF CEMENT ON TOP OF SAND WITH BAILER. 7/31/2009 RIPPED PIPE OFF AT 2720', PULLED CASING TO 850' SPOTTED 35 SXS OF CEMENT WITH 3% CC WAITED 1.5 HOURS AND TAGGED CEMENT AT 700'. PULLED CASING TO 350' AND CIRCULATED TO SURFACE WITH 145 SXS OF CEMENT WITH 3% CC.

Perfs:

Top	Bot	Thru	Comments
3770	3780		

RECEIVED
9/30/09
2010060293


RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: QUALITY CEMENTING CO. TICKET #2480 60/40/4% GEL - POS MIX WITH 3% CC

Plugged through: CSG

District: 02

Signed



(TECHNICIAN)

1/16

