

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-051-03193-00-00  
Spot: SWNWNW Sec/Twnshp/Rge: 13-15S-18W  
4290 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: LEIKER Well #: 2  
County: ELLIS Total Vertical Depth: 3589 feet

Operator License No.: 30762  
Op Name: OIL COMPANY OF AMERICA, INC.  
Address: 1200 MAIN STE 101  
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1168	0	w/unknown sxs cmt
PROD	5.5	3585	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/24/2009 10:00 AM  
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC  
Proposal Rcvd. from: ROGER MOSES Company: OIL COMPANY OF AMERICA, INC. Phone: (785) 625-9282

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 450# hulls.  
116.84

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/24/2009 1:00 PM KCC Agent: RAY DINKEL

**Actual Plugging Report:**

Hooked to 5 1/2" - pumped 50 sxs cement - followed with 320 sxs cement with 500# hulls mixed in.  
Max. P.S.I. 1000#. S.I.P. 800#.  
Hooked up to Braden head and pumped 65 sxs cement.  
Max. P.S.I. 500#. S.I.P. 200#.

**Perfs:**

INVOICED  
9-30-09  
2010060298

RECEIVED  
AUG 27 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #38534.

Plugged through: CSG

District: 04

Signed Ray A. Dinkel

(TECHNICIAN)

CM

AUG 25 2009

*PKJ*

ALPINE OIL & ROYALTY

#2

LEIKER

13-15-18W  
SW NW NW

Contr. ALPINE OIL & ROYALTY

ELLIS

County

E. 2018RB

Comm.

Comp.

4-16-54

IP

511 BOPD

Tops	Depth	Datum
ANH	1162	856
HEEB	3247	-1229
LANS	3295	-1277
CONG	3567	-1549
ARB	3583	-1565
TD	3591	-1573

Casing

8" 1168

5" 3585


DST 3438-74/1 HR, 185' H

0 & GOM, 61' FREE OIL,

BHP 915#:

DD 3591: SWB 5 BOPH/6 HRS

LEIKER EAST POOL



INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS