

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-03202-00-00
Spot: NWSWN Sec/Twnshp/Rge: 13-15S-18W
3630 feet from S Section Line, 4950 feet from E Section Line
Lease Name: LEIKER Well #: 12
County: ELLIS Total Vertical Depth: 3620 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 101
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1174	9	w/unknown sxs cmt
PROD	5.5	3619	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/25/2009 9:00 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: ROGER MOSES Company: OIL COMPANY OF AMERICA, INC. Phone: (785) 625-9282

Proposed Plugging Method: Ordered 375 sxs 60/40 pozmix - 4% gel - 500# hulls.
117.65

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/25/2009 11:00 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Cut casing at 1960'.
Pulled casing to 1750' - pumped 150 sxs cement with 300# hull mixed in.
Pulled casing to 1175' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 550' - pumped 40 sxs cement with 100# hulls.
Pulled casing to 150' - pumped 75 sxs cement - cement circulated to pit.
POOH. The cellar stayed full of cement.

Perfs:

9/30/09
2010060298

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #37550.

Plugged through: CSG

District: 04

Signed Ray Dinkel
(TECHNICIAN) CM

AUG 26 2009

ALPINE OIL & ROYALTY #12 LEIKER

13-15-18W
NW SW NW

Contr. QUAKER DRLG ELLIS County

E 2017RB Comm. 3-8-57 IP 483 BOPD/LANS
PHY POT

Tops	Depth	Datum
ANH	1162	855
HEEB	3251	-1234
LANS	3299	-1282
CONG	3540	-1523
TD	3620	-1603

Casing

8" 1174
5" 3619

DST 3309-30/1 HR, 180' HO & GCM, 120'
FR 0, 5' WTR, BHP 360#
DST 3445-85/1 HR, 750' MDY GSY OIL, BHP
475#
CO 3582: PERF 30/3459-64: ACID 1000
SWB 20 BOPH/6 HRS, NW

LEIKER E POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS