

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-19105-00-00
Spot: NWNWNWNW Sec/Twnshp/Rge: 13-15S-18W
4989 feet from S Section Line, 5012 feet from E Section Line
Lease Name: LEIKER T S TWIN TO 1 Well #: 6
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 30762
Op Name: OIL COMPANY OF AMERICA, INC.
Address: 1200 MAIN STE 101
HAYS, KS 67601

| String | Size | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF | 8.625 | 1162 | 0 | 550 SX |
| PROD | 5.5 | 3599 | 0 | 150 SX |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/06/2009 9:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: DARREL HERL Company: OIL COMPANY OF AMERICA, INC. Phone: (785) 623-6771

Proposed Method: Ordered 400 sxs 60/40 pozmix - 4% gel.
Plugging Method: Tried to get down well with pump and power swivel for two days.
Method: Stopped making hole at 1170' - decided to plug from there.

117.00

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 08/08/2009 4:30 AM KCC Agent: RAY DINKEL

Actual Plugging Report:

08/06/2009 - Case Morris approved the following plugging.
Drilled down to 1170'.
08/08/2009 - Hooked up to tubing and pumped 200 sxs cement.
Cement circulated to surface.
Backed off tubing five joints down.
Hooked up to casing - pumped 15 sxs cement and circulated out of Braden head.
Shut the Braden head and pressured up to 400#.
Left 33 joints of 2 7/8" tubing, bit, and sub in well.

Perfs:

9-30-09
2010060298

RECEIVED
AUG 21 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #037599.

Plugged through: TBG

District: 04

Signed Ray A Dinkel
(TECHNICIAN)

CM


AUG 14 2009

RET

ALPINE OIL & ROYALTY #6 LEIKER 13-15-18W
 (TWIN TO #1) NW NW NW
 Contr. QUAKER DRILLING ELLIS County
 E 2019R Comm. Comp. 8-12-55 IP 2282 BOPD

| Tops | Depth | Datum |
|------|-------|-------|
| ANH | 1153 | 866 |
| HEEB | 3249 | -1230 |
| LANS | 3296 | -1277 |
| CONG | 3562 | -1543 |
| ARB | 3597 | -1578 |
| TD | 3600 | -1581 |

Casing
 5" 3599
 DST 3304-30/1 HR, 105' HO &
 GCM, 2000' GSY OIL, BHP 705#
 DST 3357-73/1 HR, 1505' SW,
 BHP 600#: DST 3468-64/1 HR,
 1500' GAS, 62' 0" GCM, 120'
 HO & GCM, BHP 1125#: PERF
 42/3320-27: 2100' OIH/12 HR
 SWB 4 BOPH/2 HR, NATL: ACID
 LEIKER E POOL 500: SWB
 159 BO/5 HR



INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS