

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24949-00-00
Spot: SENENENW Sec/Twnshp/Rge: 26-16S-24W
350 feet from N Section Line, 2560 feet from W Section Line
Lease Name: RFDB Well #: 1
County: NESS Total Vertical Depth: 4656 feet

Operator License No.: 30742
Op Name: PALOMINO PETROLEUM, INC.
Address: 4924 SE 84TH ST
NEWTON, KS 67114

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	263		WITH 150 SX CMT

151.32

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 09/21/2009 8:30 PM
Plug Co. License No.: 34233 Plug Co. Name: MAVERICK DRILLING LLC
Proposal Rcvd. from: MARK DIPMAN Company: MAVERICK DRILLING LLC Phone: (316) 262-6700

Proposed Plugging Method: 1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Plugging Proposal Received By: JERRY W. STAPLETON WitnessType: NONE
Date/Time Plugging Completed: 08/21/2009 10:30 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

1ST PLUG AT 1890' WITH 50 SX CMT. 2ND PLUG AT 1170' WITH 80 SX CMT. 3RD PLUG AT 600' WITH 50 SX CMT. 4TH PLUG AT 300' WITH 40 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. NO MOUSE HOLE.

Perfs:

INVOICED
DATE: 9-30-09
AMOUNT: 2010060300

Remarks: USED 60/40 POZMIX 4% GEL 1/4 # FLO SEAL BY QUALITY OILWELL CEMENTING.

Plugged through: DP

RECEIVED
AUG 31 2009
KCC WICHITA

District: 01

Signed Jerry W. Stapleton
(TECHNICIAN)

RECEIVED

AUG 24 2009

KCC DODGE CITY

Form CP 25
PKT