

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-19062-00-00
Spot: SEWN Sec/Twnshp/Rge: 14-17S-4E
4401 feet from S Section Line, 1626 feet from E Section Line
Lease Name: FALK B Well #: 4
County: MARION Total Vertical Depth: 2353feet

Operator License No.: 34065
Op Name: RANDON PRODUCTION CO INC.
Address: 2761 REMINGTON RD
MARION, KS 66861

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	207		180 SX
PROD	4.5	2353		50 SX

76.47

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: _____
Plug Co. License No.: _____ Plug Co. Name: _____
Proposal Rcvd. from: RANDY SVITAK Company: RANDON PRODUCTION Phone: (620) 381-1856

Proposed Plugging Method: SAND TO 2300' CAP W/5 SXS CMT, SHOOT & PULL CASING. RUN TUBING TO 257' AND CIRCULATE CEMENT TO SURFACE

Plugging Proposal Received By: _____ Witness Type: PARTIAL
Date/Time Plugging Completed: 07/23/2009 3:00 PM KCC Agent: SHANE JONES

Actual Plugging Report:
JUNE, RANDON SANDED OFF BOTTOM & CAPPED W/5 SXS. SHUT DOWN FOR HARVEST. 7/22/2009 RANDON SHOT OFF CASING AT 1022' & PULLED IT. 7/23/2009 RANDON RAN TUBING DOWN TO APPROX 257' & CIRCULATED CEMENT TO SURFACE 87 SXS 60/40 POS W/4% GEL. I CHECKED TOP PLUG 7/24/2009 APPROX 30' DOWN. SPOKE TO RANDY SVITAK ABOUT DRY SACKING CEMENT TO SURFACE. PLUGGING NOT WITNESSED DUE TO PRIOR APPOINTMENTS

Perfs:
9-30-09
2010060301

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks:
Plugged through: TBG

District: 02 Signed [Signature] (TECHNICIAN)

JK

PKT