

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-23070-00-00
Spot: SENESE Sec/Twnshp/Rge: 28-7S-23W
1670 feet from S Section Line, 345 feet from E Section Line
Lease Name: GOEKEN Well #: 28-1
County: GRAHAM Total Vertical Depth: 3880 feet

Operator License No.: 6861
Op Name: RON'S OIL OPERATIONS INC
Address: 1889 200TH AVE
PENOKEE, KS 67659

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	260	0	160 SX CMT.
T1	2.375	3855		126.10
PROD	4.5	3876	0	535 SX CMT.

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/27/2009 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: TERRY GARRISON Company: RON'S OIL OPERATIONS INC. Phone: (785) 421-2315

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.

Plugging Proposal Received By: BRUCE BASYE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/27/2009 11:30 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto 4 1/2" - pumped 200 sxs cement with 400# hulls.
Shut in 500# P.S.I.
Tied onto backside - full.
Shut in 300# P.S.I.

Perfs:

Top	Bot	Thru	Comments
3846	3848		
3836	3839		

9-30-09
2010060305

RECEIVED
AUG 31 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed CM Mills
(TECHNICIAN)

CM PKT

AUG 27 2009

replacement card

RON'S OIL OPERATIONS
PENOKEE KS 67659

28-07S-23W
1670' FSL & 345' FEL, SEC

#28-1 GOEKEN

site 2-3/4 N & 1-1/2 W OF HILL CITY KS	co: GRAHAM	API 15-065-23070
contr: ANDERSON DRILLING #1	field: FABRICIUS EXT (1/4 W)	
geol: ROD TREMBLAY		
fr date 06/07/2005	spd date 06/23/2005	drig comp 06/30/2006
	card issued 01/23/2006	last revised 07/17/2006

ELV: 2388 KB, 2383 GL
 topsdepth/datum
 RTD3880 -1492
 NO TOPS RPTD
 LOGGED

IP status:
 OIL, P 1 BO & 50 BWPD, LKC 3836-3848 OA, 07/28/2005
 INFO RELEASED: 7/17/2006 - WAS TEMP ABD
 CSG: 8-5/8" 260 / 160 SX (ALT 2), 4-1/2" 3876 / 535 SX
 COMMENT: MI & RURT 6/22/2005
 NO CORES
 DSTS TAKEN - DETAILS NA
 TRGT ZN: LKC (OIL), PTD 3850 (LKC), MICT - CO, PF (KC)
 3836-3839, 3846-3848, W / 4 SPF, AC 2000 GAL, SWB LD, SO,
 SET 2-3/8" TBG AT 3855, NO PKR, POP, IPP 1 BO & 50
 BWPD (GR 32), DOFP 7/28/2005 - NO OTHER INFO
 AVAILABLE

COPYRIGHT 2006
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS