

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-00058-00-00
Spot: NESW Sec/Twnshp/Rge: 8-34S-32W
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: CONDIT Well #: 1
County: SEWARD Total Vertical Depth: 6503 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PKWY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5890		WITH 2 SX CMT
SURF	8.625	1565		WITH 750 SX CMT
PROD	5.5	6110	2308	WITH 200 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/11/2009 2:00 PM
Plug Co. License No.: 34091 Plug Co. Name: BLACKHAWK WELL SERVICE, LLC
Proposal Rcvd. from: BARRY WALTERS Company: BLACKHAWK WELL SERVICE, LL Phone: (785) 623-1066

Proposed Plugging Method: SAND ABCK TO 5890' WITH 5 SX CMT OR SET CIBP @ 5890' WITH 2 SX CMT. LOAD HOLE WITH GEL WATER & 50 SX CMT @ 1590'. PLUG AT 700' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

211.35

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2009 4:15 PM KCC Agent: LINDLEY REIMER

Actual Plugging Report:

CIBP @ 5890' & 2 SX CMT. 1ST PLUG AT 1595' WITH 50 SX CMT. 2ND PLUG AT 704' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 15 SX CMT. CMT CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
5942	5956		

RECEIVED
9-30-09
2010060299
KANSAS CORPORATION COMMISSION
AUG 24 2009

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY SERVICES.

Plugged through: CSG

District: 01

Signed _____

(TECHNICIAN)