

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-21008-00-01
Spot: SWSESE Sec/Twnshp/Rge: 4-16S-14W
330 feet from S Section Line, 660 feet from E Section Line
Lease Name: POPP Well #: 1
County: BARTON Total Vertical Depth: 3482 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	293	0	175 SX CMT
PROD	4.5	3480	0	125 SX CMT <u>113.17</u>

Well Type: EOR UIC Docket No: E19049.1 Date/Time to Plug: 08/12/2009 10:00 AM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: GARY SHARP Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls - 9 sxs gel.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/12/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Perfed at 930' - 540' - 150'.
Ran tubing to 3000' - tied to tubing - pumped 9 sxs gel - pumped 50 sxs cement with 100# hulls.
Pulled tubing to 1550' - pumped 100 sxs cement with 200# hulls.
Pulled tubing to 475' - pumped 55 sxs cement - circulated out 5 1/2" with cement. Shut in.
Pumped 35 sxs cement - circulated out backside.
Pulled tubing - topped off with 5 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3379	3388		
3299	3341		

9-30-09
2010060309

KANSAS CORPORATION COMMISSION

AUG 24 2009

RECEIVED

Remarks: QUALITY OIL WELL CEMENTING COMPANY-TICKET #3328.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM
PCT

Form CP-2/3

AUG 18 2009

