

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-047-21189-00-00  
Spot: NWNWNE Sec/Twnshp/Rge: 34-25S-16W  
4950 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: GIBSON Well #: 1-B  
County: EDWARDS Total Vertical Depth: 4475 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	411		WITH 275 SX CMT
PROD	4.5	4474	1400	WITH 200 SX CMT <u>145.44</u>

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2009 12:40 PM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE, INC. Phone: (620) 672-2531

Proposed Plugging Method: SAND PERFS 50' ABOVE PERFS WITH 4 SX CMT. PLUG AT 1040' IWHT 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 15 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/11/2009 2:00 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SANDED TO 4370' & 4 SX CMT WITH BAILER. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 1067' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 15 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4422	4432		

KANSAS CORPORATION COMMISSION  
AUG 26 2009  
RECEIVED  
INVOICED  
DATE 10-1-09  
INV. NO. 2010060311

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed Richard W. Lacey  
(TECHNICIAN)

RECEIVED  
AUG 18 2009  
KCC DODGE CITY

Form CP 2/3