


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Rooks _____ County. Sec. 26 Twp. 10S Rge. _____ (E) 19 (W) _____
Location as "NE/CNW/SW" or footage from lines. NE NE SW
Lease Owner NADEL & GUSSMAN
Lease Name HERREN Well No. 1
Office Address 625 UNION CENTER, WICHITA, KANSAS
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MAY 2, 1966
Application for plugging filed (PHONE 5/2/66) MAY 9, 1966
Application for plugging approved MAY 2, 1966
Plugging commenced MAY 2, 1966
Plugging completed MAY 2, 1966

Reason for abandonment of well or producing formation _____
If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well LEO MASSEY
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3613 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	214	8-5/8	214'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 500 FEET. SET FIRST PLUG AT 500 FT. W/25 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 210 FEET. SET SECOND PLUG AT 210 FT. W/20 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 40 FEET. SET THIRD PLUG AT 40 FT. W/10 SACKS CEMENT.
JOB BY HALLIBURTON CO. JOB COMPLETE AT 12:00 NOON ON MAY 2, 1966, PLUGGED RAT HOLE W/2 SACKS CEMENT.

RECEIVED
STATE CORPORATION COMMISSION
5-18-66
MAY 18 1966
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor GABBERT-JONES, INC.
Address 514 ORPHEUM BLDG., WICHITA, KANSAS

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. E. Hall
514 ORPHEUM BLDG., WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 9TH day of MAY, 19 66

My commission expires FEBRUARY 1, 1968
Barbara J. Layton
BARBARA J. LAYTON Notary Public.

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

HERREN #1
 NE NE SW SECTION 26-10S-19W
 ROOKS COUNTY, KANSAS

COMMENCED: APRIL 21, 1966
 COMPLETED: MAY 2, 1966

OPERATOR - NADEL & GUSMAN

DEPTH		FORMATION	REMARKS
FROM	TO		
0	70	POST ROCK AND SAND	RAN 10 JOINTS OF 3-5/8" CASING, SET @ 214' w/170 BAGGED CEMENT.
70	214	SHALE AND SHELLS	
214	600	SHALE AND SHELLS	
600	690	SAND	
690	750	SHALE	
750	1305	SAND AND SHALE	
1305	1370	SHALE	
1370	1400	ANHYDRITE	
1400	2015	SHALE	
2015	2660	LIME AND SHALE	
2660	2915	LIME	
2915	3218	LIME AND SHALE	
3218	3481	LIME	
3481	3521	CHERTY LIME	
3521	3594	CHERTY CONGLOMERATE	
3594	3613	LIME	
3613	TO		DRY AND ABANDONED.

RECEIVED
 STATE CORPORATION COMMISSION
 MAY 17 1966
 CONSERVATION DIVISION
 WICHITA, KANSAS

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE NE NE SW SECTION 26-10S-19W, ROOKS COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall

 E. E. HALL

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 9TH DAY OF MAY, 1966, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton

 BARBARA J. LAYTON, NOTARY PUBLIC

My Commission Expires February 1, 1968.