

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
2-14-72
FEP 14 1972
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ehrlich of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Ehrlich guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co.

Complete Address: 617 Union Center Wichita, Ks.

Lease Name: Johnson "G" Well No. 2

Location: SW NW SE Sec. 26 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3460" Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Ehrlich was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 660' and displace
70 sk cmt thru drill pipe. Heavy mud to 180' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo A. Murray
Conservation Division Agent