



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 8 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Burkhart of Sage Drlg. has this
date requested permission to plug the following described well:

Mr. Burkhart guarantees payment of the plugging fee.

Operator's full Name: Beacon Resources Corp.

Complete Address: Suite 1000 Century Bldg., Wichita, Ks.

Lease Name: Sutor Well No. 2

Location: NW SW SE Sec. 27 Twp. 10 Rge. (E)(W) 19

County: Rooks Total Depth 3687' Oil Well

Gas Well Input Well SWD Well D & A XXX Lost Hole

Mr. Burkhart was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 800' and displace
70 sk cmt thru drill pipe. Heavy mud to 210' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Leo J. Massey
Conservation Division Agent